

Waverly Office Building

North Augusta, South Carolina

Compacted Aggregate Piers (AMPier)

Compacted aggregate piers (AMPier) were installed to support a new office building. Uplift anchors were also installed for some of the central foundations. Aggregate piers will provide 8,000 psf bearing capacity for the spread foundations.



GC: Shelco Construction
Geotechnical Contractor: WEC