

Courtyard Hotel

Greenville, SC

A total of twenty-eight rock anchors were constructed for uplift resistance. Individual rock anchors were extended at least 20 ft into the ground. The uplift anchors were constructed of 1-3/8", GR 150, epoxy coated thread bar and 4,000 psi grout.



GC: Triangle Construction
Geotechnical Contractor: WEC