

UPS Distribution Facility

Asheville, North Carolina

Expansion of the UPS Distribution Facility required a new parking lot to be constructed. One side of the parking lot was cut into a hillside. WEC proposed a permanent soil nail wall in-lieu of the specified cast-in-place concrete retaining wall resulting in considerable cost savings.

DrainGreat, a product patented and sold exclusively by WEC was used to collect ground water and carry it away from the wall. You can obtain more information at www.draingreat.com.

The finished shotcrete has a relatively planer, “gun finish”. This finish reflects very little light and blends into the landscape better than cast-in-place walls.

Grading Contractor: Young & McQueen Grading Co, Inc.
Geotechnical Contractor: WEC

